

भारतीय सर्वेक्षण विभाग
SURVEY OF INDIA

दूरभाष) 0135 2747623
Telephone) 0135 2742015
श्रीकृति
Fax:) 91-135-2747291
E-mail: admn.soi@gov.in



राष्ट्रीय भू-स्थानिक आंकड़ा केंद्र
NATIONAL GEO-SPATIAL DATA CENTRE
ब्लॉक 6, हाथीबड़कला इस्टेट, पत्र बेंटी सं. 200
Block 6, Hathibarkala Estate, Post Box No. 200
देहरादून (उत्तराखण्ड) Dehra Dun- 248001 (Uttarakhand)

No. 25 /15-C-STPI

दिनांक Dated 12 -01-2016

To,

M/S

Sub :- INVITATION OF SEALED TENDER FOR LAN TO BE ESTABLISHED AT NGDC, SURVEY OF INDIA CAMPUS.

Sir,

Scaled tenders are invited from the firms having office at Uttarakhand for LAN to be established at NGDC computer halls (4 halls with around 60 computers). The successful tenderer will have to establish LAN with CAT VI cables, I/O boxes of make Dlink and switches of make Dlink, or having the same standards.

Approximate number of items to be used for LAN establishment are shown in attached Annexure 'A'. The quantity of the items may vary.

The description of the job is as follows:-

All existing LAN cables are to be removed.
All cables are to be placed below false flooring and in PVC conduits.
Tender will have to submit proposed networking diagram.
All switches used, are to be placed properly in racks with lock.

The job will be awarded to the firm with quotation of minimum amount of the job shown at Sl. 8 of the Annexure "A" as **Total Price**.

Last date for receiving the tender is 08th February 2016 at 15:00 hours.

The bidder can inspect the site on any working day before 08th February 2016 between 9:30 hrs. to 17:00 hrs.

The Director, NGDC reserves the right to reject any or all tenders without assigning any reason thereof.

Encl: As above

Yours Sincerely

(R. S. Rawat)
Officer Surveyor
for Director, NGDC

ANNEXURE "A"

Sl.No.	Particulars	Approximate Units	Rate	Tax	Total Price
1.	Switch D-Link (24 Port)	01 No.			
2.	Switch D-Link (16 Port)	02 Nos.			
3.	Switch D-Link (08 Port)	01 No.			
4.	Rack 6U D-Link with all accessories	03 Nos.			
5.	I/O Box D-Link (Cat 6)	60 Nos.			
6.	LAN Cable (Cat 6) Box 305 Mtr.	04 Nos.			
7.	Installation of network including laying of cable with RJ-45 connectors Cat 06, pipe fitting with other accessories, removing of existing cables and testing of network.	One job			
8.	Total				

Terms & Conditions (if any):-